

Dam: Amata

Country Mexico

River San Lorenzo

24°30'39.73"N 106°55'29.76"W

24.511036 -106.924934

Owner/Client CFE (Comisión Federal de Electricidad)

Designer/Engineer Comisión Federal de Electricidad

Contractor Desarrollo Canoras/Inmobiliaria Canoras JV

Purpose (code) I

Site start 18.11.2003

RCC start 01.11.2004

RCC completion 30.04.2005

Site completion 30.06.2005

Height (m) 30

Length (m) 218

Volume of RCC ( $m^3 \times 10^3$ ) 42

Total volume ( $m^3 \times 10^3$ ) 60

Reservoir capacity ( $m^3 \times 10^6$ ) 14

Upstream slope V  
1.00

Forming of upstream face (code) (8)

Downstream slope 1.00

Forming of downstream face (code) (3) \*

Spillway slope 1.00

Forming of spillway face (code) (12)

Depth of layers (mm) 300

Depth of lifts (mm) 300

Cement content ( $kg/m^3$ ) 120

Pozzolan content ( $kg/m^3$ ) 0

Code for pozzolan (-)

RCCDAM Unique Serial No. RCCDAM0334

## Under Construction



RCCDAM0334UC

## Completed Dam



RCCDAM0334CD

## Google Earth



RCCDAM0334GE

# Guide to Abbreviations

## Purpose

- E Environmental
- F Flood control
- G Groundwater recharge
- H Flood control
- I Irrigation
- N Navigation
- P Pollution control
- R Recreation
- W Water supply

## Facing method

- (1) Traditional concrete against formwork
- (2) Traditional concrete against formwork with external geomembrane
- (3) RCC against formwork
- (4) RCC against formwork with external geomembrane
- (5) Traditional concrete against precast concrete panels
- (6) Traditional concrete against precast concrete panels with geomembrane
- (7) RCC against precast concrete panels
- (8) RCC against precast concrete panels with geomembrane
- (9) RCC against precast concrete panels with hot poured membrane
- (10) RCC against precast concrete blocks
- (11) Reinforced conventional concrete cast before RCC placement
- (12) Reinforced conventional concrete cast after RCC placement
- (13) Reinforced concrete cast against precast units or slip-formed facing elements
- (14) Slip-formed/extruded facing elements
- (15) RCC supported by fill shoulders
- (16) Mechanically compacted unformed face of RCC
- (17) Unformed face of RCC
  - ' GEVR/GE-RCC
  - \* Stepped face

## Pozzolans

- (-) No Pozzolan Used
- (C) High-lime flyash (ASTM Class C)
- (F) Low-lime flyash (ASTM Class F)
- (M) Milled sand
- (N) Natural pozzolan (ASTM Class N)
- (R) ROLAC (mixture of flyash and slag with or without limestone fines)
- (S) Ground-granulated blast-furnace slag
- (L) Mixture of GGBFS and limestone fines