

Dam: Dyraaba (part of Uma Oya Project)

Country Sri Lanka

River Mathatilla Oya

6°53'12.98"N 80°57'22.73"E

6.886939 80.956314

Owner/Client Ministry of Irrigation and Water Resources Management

Designer/Engineer *Unknown*

Contractor Farab Company, Iran (sub-Contracted to Ev-Yol Construction Co.)

Purpose (code) H I

Site start 01.01.2011

RCC start 01.01.2013

RCC completion 31.12.2017

Site completion 31.12.2018

Height (m) 50

Length (m) 165

Volume of RCC ($m^3 \times 10^3$) 40

Total volume ($m^3 \times 10^3$) 50

Reservoir capacity ($m^3 \times 10^6$) 1

Upstream slope V

Forming of upstream face (code) (1)

Downstream slope *Unknown*

Forming of downstream face (code) (1) *

Spillway slope *Unknown*

Forming of spillway face (code) (12)

Depth of layers (mm) 300

Depth of lifts (mm) 300

Cement content (kg/m^3) 95

Pozzolan content (kg/m^3) 95

Code for pozzolan (F)

RCCDAM Unique Serial No. RCCDAM0650

Under Construction



RCCDAM0650UC

Completed Dam



RCCDAM0650CD

Google Earth



RCCDAM0650GE

Guide to Abbreviations

Purpose

- E Environmental
- F Flood control
- G Groundwater recharge
- H Flood control
- I Irrigation
- N Navigation
- P Pollution control
- R Recreation
- W Water supply

Facing method

- (1) Traditional concrete against formwork
- (2) Traditional concrete against formwork with external geomembrane
- (3) RCC against formwork
- (4) RCC against formwork with external geomembrane
- (5) Traditional concrete against precast concrete panels
- (6) Traditional concrete against precast concrete panels with geomembrane
- (7) RCC against precast concrete panels
- (8) RCC against precast concrete panels with geomembrane
- (9) RCC against precast concrete panels with hot poured membrane
- (10) RCC against precast concrete blocks
- (11) Reinforced conventional concrete cast before RCC placement
- (12) Reinforced conventional concrete cast after RCC placement
- (13) Reinforced concrete cast against precast units or slip-formed facing elements
- (14) Slip-formed/extruded facing elements
- (15) RCC supported by fill shoulders
- (16) Mechanically compacted unformed face of RCC
- (17) Unformed face of RCC
 - ' GEVR/GE-RCC
 - * Stepped face

Pozzolans

- (-) No Pozzolan Used
- (C) High-lime flyash (ASTM Class C)
- (F) Low-lime flyash (ASTM Class F)
- (M) Milled sand
- (N) Natural pozzolan (ASTM Class N)
- (R) ROLAC (mixture of flyash and slag with or without limestone fines)
- (S) Ground-granulated blast-furnace slag
- (L) Mixture of GGBFS and limestone fines