

Dam: Minas San Francisco

Country Ecuador

River Jubones

3°18'58"S 79°28'53.18"W

-3.31611 -79.481438

Owner/Client Celec Ererjubones Cp

Designer/Engineer Geodata-Astec

Contractor Harbin Electric International

Purpose (code) H

Site start 01.12.2011

RCC start 01.01.2014

RCC completion 31.12.2017

Site completion 31.01.2019

Height (m) 78

Length (m) 209

Volume of RCC (m³x10³) Unknown

Total volume (m³x10³) Unknown

Reservoir capacity (m³x10⁶) 14

Upstream slope Unknown

Forming of upstream face (code) Unknown

Downstream slope Unknown

Forming of downstream face (code) Unknown

Spillway slope Unknown

Forming of spillway face (code) Unknown

Depth of layers (mm) 300

Depth of lifts (mm) 300

Cement content (kg/m³) Unknown

Pozzolan content (kg/m³) Unknown

Code for pozzolan Unknown

RCCDAM Unique Serial No. RCCDAM0894

Under Construction



RCCDAM0894UC

Completed Dam



RCCDAM0894CD

Guide to Abbreviations

Purpose

- E Environmental
- F Flood control
- G Groundwater recharge
- H Flood control
- I Irrigation
- N Navigation
- P Pollution control
- R Recreation
- W Water supply

Facing method

- (1) Traditional concrete against formwork
- (2) Traditional concrete against formwork with external geomembrane
- (3) RCC against formwork
- (4) RCC against formwork with external geomembrane
- (5) Traditional concrete against precast concrete panels
- (6) Traditional concrete against precast concrete panels with geomembrane
- (7) RCC against precast concrete panels
- (8) RCC against precast concrete panels with geomembrane
- (9) RCC against precast concrete panels with hot poured membrane
- (10) RCC against precast concrete blocks
- (11) Reinforced conventional concrete cast before RCC placement
- (12) Reinforced conventional concrete cast after RCC placement
- (13) Reinforced concrete cast against precast units or slip-formed facing elements
- (14) Slip-formed/extruded facing elements
- (15) RCC supported by fill shoulders
- (16) Mechanically compacted unformed face of RCC
- (17) Unformed face of RCC
 - ' GEVR/GE-RCC
 - * Stepped face

Pozzolans

- (-) No Pozzolan Used
- (C) High-lime flyash (ASTM Class C)
- (F) Low-lime flyash (ASTM Class F)
- (M) Milled sand
- (N) Natural pozzolan (ASTM Class N)
- (R) ROLAC (mixture of flyash and slag with or without limestone fines)
- (S) Ground-granulated blast-furnace slag
- (L) Mixture of GGBFS and limestone fines